


HEAD OFFICE

303 Church Street
 Private Bag X 44
 MOGWADI 0715
 Telephone : (015) 501 0243/4
 Fax no : (015) 501 0419
 E-mail: info@molemole.gov.za



Molemole Municipality

ALL CORRESPONDENCE TO BE ADDRESSED TO THE MUNICIPAL MANAGER

MOREBENG BRANCH OFFICE

25 Cnr. Roets & Viviers Street
 MOREBENG 0810
 Telephone : (015) 397 4333 / (015) 397 4327
 Fax no : (015) 397 4334

www.molemole.gov.za

Enquiries: Mashatola D

Reference: TECH: 8/1/1:03

01 September 2017

MOLEMOLE MUNICIPALITY IS HEREBY INVITING QUOTATIONS FROM PROSPECTIVE SERVICES PROVIDERS WHO ARE REGISTERED ON THE CENTRAL SUPPLIER DATABASE FOR THE AS MAINTENANCE OF MOHODI (FATIMA) INTERNAL STREET AND STORMWATER PER THE BELOW SPECIFICATION

Description	Units	QTY	Rate	Amount
Social Obligations				
a) Provisional Sum for the payment of the CLO (R4000.00)	Prov. Sum			R 8000-00
Handling Cost of the Above Item.	%			R 800-00
a) Provisional Sum for Cost of attending Project Steering Committee meetings (5 committee members R1500.00)	Prov. Sum			R 1500-00
Handling Cost of the Above Item.	%			R 150-00
Prefabricated Culverts				
1. Excavation:				
Excavating materials situated within the following depth ranges below the surface level:				
(i) 0m up to 1.5m	m ³	40		
2. Backfilling and compaction to 95% MOD ASHTO using the following:				
(a) Excavated Materials	m ³	40		
(b) Imported Materials	m ³	150		
3. Concrete Pipe Culverts:				
(b) on Class B bedding:				
(ii) 900mm dia. (Class 100D)	m	40		
10. Cast in-situ Concrete and Formwork: in 150mm inlet and outlet structures, skewed ends, wing walls, catchpits, thrust and anchor blocks Class U2 finish for (i) Class 25/19 concrete and concrete testing	m ³	40		
11. Reinforcing Steel using:				

Vision: A developmental people driven organization that serves its people"

Mission: To provide essential and sustainable services in an efficient and effective manner.

(a) Welded Steel Fabric - Mesh Ref. No. 880	kg	600		
(b) Welded Steel Fabric - Mesh Ref. No. 395	kg	300		
15. MASS EARTHWORKS				
(a) Pavement layers constructed from gravel taken from cut or borrow, including free-haul up to 6,0 km				
(a) Gravel sub base layer compacted to:				
(i) 93% of modified AASHTO density, compacted layer thickness 150mm	m ³	800		
(c) Gravel base (unstabilized gravel) compacted to:				
(ii) 95% of modified AASHTO density, compacted layer thickness 150 mm	m ³	200		
16. ROAD SIGNS				
Aluminium sheet regulatory warning and information signs with Steel Support (Bridge Ahead Sign not exceeding 2 m2)	No	2		
Retro reflective danger plates double sided with steel support (Red and White)	No.	2		
Subtotal				
V.A.T @ 14 %				
Total project cost (Including V.A.T)				

The following documentation should accompany the proposal:

- a) Recent supplier registration summary report (CSD report) { Last verified a month before the closing date}
- b) Certified copy of B-BBEE certificate
- c) Certified TAX clearance certificate
- d) CIDB Grade 1CE
- e) A full completed and signed declaration of interest form which is downloaded from www.molemole.gov.za
- f) A fully complete and signed SBD form also downloaded from www.molemole.gov.za

Vision: A developmental people driven organization that serves its people"


Mission: To provide essential and sustainable services in an efficient and effective manner.

The following conditions will apply

- a) Quotation must be on an official letterhead of the company;
- b) Price(s) quoted must be valid for at least thirty (30) days from the date of this offer;
- c) Price (s) must be firm and inclusive of VAT;
- d) Delivery must be made within 14 days. Failure to deliver within 14 day may result in the municipality cancelling its order.
- e) Quotations will be evaluated on 80/20 preference point system. Whereas 80 points will be for price and 20 for preference as per PPPFA of 2000, BBBEEA of 2003 and preferential procurement regulation of 2001;
- f) Payment will be effected within 30 days of receipt of invoice.

Kindly direct all technical enquiries to **Mr. Mabasa V.P** at **015 501 2323** between 08:00 and 16:00. All proposals should be submitted at Mogwadi Municipal Tender Box by the **12th September 2017** at 11H00. Clearly marking "**MAINTENANCE OF MOHODI (FATIMA) INTERNAL STREET AND STORMWATER**".

No quotation will accepted after the closing date.



MR M.W RAMOGALE
ACTING MUNICIPAL MANAGER

Vision: A developmental people driven organization that serves its people"

Mission: To provide essential and sustainable services in an efficient and effective manner.