

HEAD OFFICE

303 Church Street
Private Bag X 44
MOGWADI 0715
Telephone: (015) 501 0243/4
Fax no : (015) 501 0419
E-mail: info@molemole.gov.za



Molemole Municipality

MOREBENG BRANCH OFFICE

25 Cnr. Roets & Viviers Street
MOREBENG 0810
Telephone : (015) 501 2371
Fax no : (015) 397 4334

www.molemole.gov.za

ALL CORRESPONDENCE TO BE ADDRESSED TO THE MUNICIPAL MANAGER

Enquiries: **Ralephenya T.D**

Ref: **8/1/1/03**

24 JULY 2023

MOLEMOLE LOCAL MUNICIPALITY IS INVITING QUOTATIONS FROM SUITABLE SERVICE PROVIDERS WHO ARE LISTED ON THE CENTRAL SUPPLIER DATABASE FOR THE CONSTRUCTION OF TWO (2) NEW GUARD HOUSES AT MOREBENG BRANCH OFFICE AND TRAFFIC OFFICE AND SUPPLY AND INSTALLATION OF CARPORT AT MOLETJIE BRANCH OFFICE:

1. Specification:

Item No		Quantity	Unit	Rate - R	Amount
	<p>SECTION No.1 -Guard House</p> <p>BILL No.1</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p>NOTE: Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.104 for CPAP formula purposes</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u> The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p><u>Carting away of excavated material</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively from stock piles situated on the building site.</p> <p>EARTHWORKS</p> <p><u>EXCAVATION, FILLING, ETC.</u></p> <p><u>Excavation in earth not exceeding 2m deep</u></p>				
1	Trenches	22	m ³		
2	Soft rock	2	m ³		

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

3	Hard rock	2	m ³		
4	<u>Extra over all excavations for carting away</u> Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	22	m ³		
5	<u>Compaction of surfaces</u> Rip compaction of ground surface under surface beds etc by wetting and compacting to 935% Mod Aashto density at optimum moisture content in layers not exceeding 150mm	32	m ²		
6	<u>Prescribed density tests on filling</u> "Field Density" test including "Optimum moisture content" (4 readings/test)	2	No		
7	<u>SOIL POISONING</u> <u>Soil insecticide</u> Under floor surface beds etc including forming and poisoning shallow furrows against foundation walls etc, filling furrows and ramming	22	m ²		
8	To bottoms and sides of trenches	102	m ²		
Carried Forward to Summary of Section No.1				R	
SECTION 1: Guard House					
Bill No.1					
Earthworks (Provisional)					
2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					
Item No		Quantity	Unit	Rate	Amount
	SECTION No.1: Guard House			R	
	BILL No.2				
	<u>CONCRETE & FORMWORK</u>				
	NOTE: Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.110 for CPAP formula purposes				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Cost of tests</u> The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G, shall include the cost of providing cube moulds necessary for purpose, for testing costs and for submitting reports on the tests to the Principal Agent. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the Principal Agent. (Test cubes are measured separately)				

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

<u>Formwork</u>					
<p>Description of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself.</p> <p>Formworks to soffits of solid etc shall remain deemed to be slabs not exceeding 250mm thick unless otherwise described.</p> <p>Formwork to sides of bases, pile caps, ground beams, etc will only be measured where it is prescribed by the Engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and cost thereof shall be deemed to be included in allowance for taking the risk of collapse of sides of excavations, provision for which is made in "Earthworks".</p> <p style="text-align: center;">Carried forward</p> <p>Section No.1 Guard House Bill No.2 Concrete and Formwork 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY</p>					
					Not priced
Item No		Quantity	Unit	Rate R	Amount Not priced
Brought Forward					
<u>CONCRETE</u>					
<u>25MPa/19mm Concrete</u>					
1	Strip footing	6	m ³		
2	Surface beds	2	m ³		
<u>TESTS BLOCKS</u>					
<u>Making and testing 150 x 150 x 150mm concrete strength test cube</u>					
3		2	No		
<u>COCRETE SUBDRIES</u>					
<u>Finishing top surfaces of concrete smooth with a wood float</u>					
4	Surface beds, ramps etc, to falls	32	m ²		
<u>MOVEMENT JOINTS ETC</u>					
<u>Expansion joints with 15mm softboard between vertical concrete and brick surfaces</u>					

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

5	Not exceeding 300mm high to edges of surface beds	10	m		
Carried Forward to Summary of Section No.1				R	
Section No.1 Guard House Bill No.2 Concrete and Formwork 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					
Item No		Quantity	Unit	Rate R	Amount
Section No.1: Guard House BILL No.3 <u>MASONRY</u> NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.116 for CPAP formula purposes <u>SUPPLEMENTARY PREAMBLES</u> <u>BRICKWORK</u> <u>Sizes in description</u> Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of the brick. <u>Face bricks and Semi-face bricks</u> Bricks shall be ordered timeously to obtain uniformity in size and colour. <u>Pointing</u> Descriptions of recessed pointing to fair face brickwork and face brick shall be deemed to include square recessed, hollow recessed, weathered pointing, etc. <u>SUB-STRUCTURE</u> <u>Brickwork of NFX bricks in class II mortar</u> 1 One brick walls 26 m ² <u>SUPER STRUCTURE</u> <u>Brickwork of NFP bricks in class II mortar</u> 3 Half brick walls in beamfilling 14 m ² 4 Half brick walls 8 m ² 5 One brick walls 80 m ²					

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

	BRICKWORK SUNDRIES				
	<u>Brickwork reinforcement</u>				
6	75mm Wide reinforcement built in horizontally	56	m		
7	150mm Wide reinforcement built in horizontally	56	m		
	<u>Pre-stressed fabricated lintels</u>				
8	110 x 75mm Lintels in lengths not exceeding 3m	16	m		
	<u>Galvanised hoop iron cramps, ties, etc</u>				
9	30 x 1,6mm Roof tie 1,5m long with one end fixed to timber and other end built into brickwork	16	No		
	Carried Forward			R	
	Section No.1 Guard House Bill No.3 Masonry 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY				
Item No		Quantity	Unit	Rate	Amount
	Brought Forward			R	
	<u>FACE BRICKWORK</u>				
	<u>Face bricks (Prime Cost amount R4 500.00/1000) pointed with flush horizontal and vertical joints</u>				
10	Extra over brickwork for external face brickwork	80	m ²		
	<u>Brick-on-edge header and roller course copings, sills, etc with recessed joints on all external exposed faces</u>				
11	220mm Wide sill set sloping and slightly projecting pointed on top and front edge	4	m		
12	Brick-on-edge header and roller course lintels with recessed joints on all external exposed faces	8	m		
	Carried Forward to Summary of Section No.1			R	
	Section No.1 Guard House Bill No.3 Masonry 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY				
Item No		Quantity	Unit	Rate	Amount
	Section No.1 Guard House BILL No.4				

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

WATERPROOFING					
<p>NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.120 for CPAP formula purposes</p> <p><u>DAMP-PROOFING OF WALLS AND FLOORS</u> <u>One layer of 375 micron "Consol Plastics Brikgrip DPC" embossed damp proof course</u></p> <p>1 In walls 60 m</p> <p>2 Under surface bed 22 m²</p> <p style="text-align: right;">R</p> <p>Carried Forward to Summary of Section No.1</p> <p>Section No.1 Guard House Bill No.4 Waterproofing 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY</p>					
Item No		Quantity	Unit	Rate	Amount
<p>Section No.1 Guard House BILL No.5</p> <p><u>ROOF COVERINGS, etc</u></p> <p>NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.124 for CPAP formula purposes</p> <p><u>TILED ROOF COVERING AND ACCESSORIES</u> <u>420 x 332mm "Marley" concrete roof tiles nailed with no-corrosive tile nails to 38 x 38mm sawn softwood battens at 330mm centres on Marley under tile membrane</u></p> <p>1 Roof covering with pitch of 22° (not exceeding 25°) 32 m²</p> <p>2 Ridge tiles to match roofing tiles bedded and pointed in 1:3 cement mortar tinted to match tile colour 12 m²</p> <p style="text-align: right;">R</p> <p>Carried Forward to Summary of Section No.1</p> <p>Section No.1 Guard House Bill No.5 Roof Coverings, etc 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY</p>					

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

Item No	Quantity	Unit	Rate	Amount
<p>Section No.1 Guard House BILL No.6</p> <p><u>CARPENTRY AND JOINERY</u></p> <p>NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.126 for CPAP formula purposes</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Particle board:</u> Particle board shall comply with the following specifications a) SABS 1300 Particle board: exterior and flooring type b) SABS 1301 Particle board: interior type</p> <p><u>Joinery</u> Descriptions of frames shall be deemed to include frames, transoms, mullions, rails, etc. Descriptions of hardwood joinery shall be deemed to include pelleting of bolt holes.</p> <p><u>Fixing</u> Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete</p> <p><u>Decorative laminate finish</u> Laminate finish shall be glued under pressure. Edge strips shall be butt jointed at junctions with adjacent similar finish</p> <p><u>ROOFS, ETC</u></p> <p><u>Plate nailed timber roof truss construction</u></p> <ul style="list-style-type: none"> * The following is applicable in respect of roof trusses: * Trusses are at maximum 1050mm centres * Ceilings are generally 6,4mm gypsum plasterboard on 38 x 38mm brandering * All timber to be sawn softwood in accordance with V4 or M4 as defined in SABS 563 / SABS 1245 * Metal connector plates shall have a minimum yield strength of 228MPa and a minimum ultimate tensile strength of 330MPa with hot-dip galvanised finish * All joints to be close fitted butt joints * Trusses shall be designed by a registered supplier of prefabricated trusses who shall issue an Engineers' Certificate upon completion of installation * The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained on site prior design or fabrication commences 				

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

*** Tenderes must study the roof plan and sections as provided and obtain prices from qualified and registered roof truss supplier as no claim in this regards will be entertained**

Section No.1 Guard House
Bill No.6
Carpentry & Joinery
2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY

Item No		Quantity	Unit	Rate	Amount
	<u>Sawn Softwood</u>				
1	38 x 114mm Wall plates Design, manufacture, supply and deliver on site, plate nailed roof construction to the guard house size 16m ² overall on plan consisting of double pitch roof trusses,	28	m		
2	1800mm high (extreme), including all necessary purlins, runners, bracing and cross bracing, etc (wall plates measured elsewhere)	2	No		
	<u>Sundries</u>				
3	Two coats creosote on sawn timbers	8	m ²		
	<u>DOORS, ETC</u>				
	<u>Wrought doors hung to steel frames</u>				
4	44mm "TDM" framed and ledged door 813 x 2 032mm high	2	No		
	Carried Forward to Summary of Section No.1			R	
	Section No.1 Guard House Bill No.6 Carpentry & Joinery 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY				
Item No		Quantity	Unit	Rate	Amount
	Section No.1 Guard House BILL No.7				
	<u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u>				
	NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.129 for CPAP formula purposes				

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

<u>SUPPLEMENTARY PREAMBLES</u>					
Descriptions Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as "bolted" the bolts have been given elsewhere					
<u>NAILED UP CEILINGS</u>					
<u>4mm "Fibre cement" ceiling board with H-type pressed steel jointing strips</u>					
1	Ceilings including 38 x 38mm sawn softwood brander at min. 400mm centres	22	m ²		
2	Extra over ceiling for 650 x 650mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 50mm sawn softwood cross brander covered with ceiling board and fitted flush in opening	2	No		
<u>"Rhino" gypsum plasterboard cornices</u>					
3	75mm Coved cornices	34	m		
<u>"Aerolite" or similar and approved insulation</u>					
4	100mm thick Insulation closely fitted and laid on top of brander of ceiling	24	m ²		
Carried Forward to Summary of Section No.1					
Section No.1 Guard House					
Bill No.7					
Ceilings, Partitions and Access flooring					
2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					
Item No		Quantity	Unit	Rate	Amount
Section No.1 Guard House					
BILL No.8					
<u>IRONMONGARY</u>					
NOTE					
Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.132 for CPAP formula purposes					
<u>SUPPLEMENTARY PREAMBLES</u>					
<u>Finishes to ironmongery</u>					

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

Where applicable finishes to ironmongery are indicated by suffixes in according with the following list BS - Satin bronze lacquered, CH - Chromium plated, SC - Satin chromium plated, SE - Silver enamelled, GE - Grey enameeled, AS - Anodised silver, AB - Anodised bronze, AG - Anodised gold, ABL - Anodised black, PB - Polished brass, PL - Polished and lacquered, PT - Epoxy coated, SD - Sanded, NP - Nickle plated					
<u>HINGES, BOLTS, ETC.</u>					
1	150mm Brass barrel bolt	2	No		
<u>LOCKS</u>					
<u>"Mazac Tarpon" or similar approved</u>					
2	"LA952/4L" four lever lockset and handles with chrome plated finish	2	No		
<u>SUNDRIES</u>					
<u>"Union" or similar and approved</u>					
6	"AL8730AS" door stop plugged	2	No		
Carried Forward to Summary of Section No.1				R	
Section No. Guard House					
Bill No.8					
Ironmongary					
2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					
Item No		Quantity	Unit	Rate	Amount
Section No.1 Guard House					
BILL No.9					
<u>METALWORK</u>					
NOTE					
Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.136 for CPAP formula purposes					
<u>SUPPLEMENTARY PREAMBLES</u>					
<u>Descriptions</u>					
Descriptions of bolts shall be deemed to include nuts and washers.					

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

	<p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete.</p> <p>Metalwork described as "holed or bolt(s)" shall be deemed to exclude the bolts unless otherwise described.</p> <p><u>PRESSED STEEL DOOR FRAMES</u></p> <p><u>1.2mm Double rebated frames suitable for one brick walls</u></p> <p>2 Frame for door 813 x 2032mm High</p> <p><u>STEEL WINDOWS, DOORS, ETC.</u></p> <p><u>Standard residential windows with type "B2" burglar bars to opening and fixed sections</u></p> <p>4 W3 - Size 1200 x 1200mm</p> <p>5 W5 - Size 600 x 650mm</p> <p>Carried Forward to Summary of Section No.1</p> <p>Section No.1 Guard House Bill No.9 Metalwork</p> <p>2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY</p>	2	No		
		4	No		
		2	No		
				R	
Item No		Quantity	Unit	Rate	Amount
	<p>Section No.1 Guard House BILL No.10</p> <p><u>PLASTERING</u></p> <p>NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.142 for CPAP formula purposes</p> <p><u>SCREEDS</u></p> <p><u>1:4 Cement plaster screeds, wood floated on concrete</u></p> <p>1 30mm Thick on floors and landings</p> <p><u>INTERNAL PLASTER</u></p> <p><u>Cement plaster on brickwork</u></p> <p>2 On walls</p> <p>3 On narrow widths</p>	32	m ²		
		70	m ²		
		4	m ²		

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

	Carried Forward to Summary of Section No. 1			R	
	Section No.1 Guard House Bill No.10 Plastering 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY				
Item No		Quantity	Unit	Rate	Amount
	Section No.1 Guard House BILL No.11 <u>TILING</u> NOTE Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.144 for CPAP formula purposes <u>SUPPLEMENTARY PREAMBLES</u> <u>Descriptions</u> Unless described as "fixed with adhesive to plaster" descriptions of tiling on brick or concrete walls, columns, etc. shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc, shall be deemed to include 1:3 plaster bedding. <u>FLOOR TILING</u> <u>300 x 300mm Ceramic tiles (PC Amount R150/m²) fixed with adhesive to bedding and flush pointed with tinted waterproof jointing compound</u>				
3	On floors	22	m²		
4	On skirting	30	m		
	Carried Forward to Summary of Section No.1			R	
	Section No.1 Guard House Bill No.11 Tiling 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY				
Item No		Quantity	Unit	Rate	Amount
	Section No.1 Guard House BILL No.12 <u>PAINTWORK</u> NOTE				

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No.152 for CPAP formula purposes					
<u>ON FLOATED PLASTER</u> <u>One coat alkali resistant primer, one undercoat and two coats interior QUALITY PVA emulsion paint</u>					
1	On internal walls	70	m ²		
<u>ON PLASTERBOARD</u> <u>One coat primer and two coats interior QUALITY PVA emulsion paint</u>					
2	On ceilings and cornices	22	m ²		
<u>ON METAL</u> <u>Spot priming defects in pre-primed surfaces with zinc chromate primer and applying one undercoat and two coats matt enamel paint on steel</u>					
3	On windows	4	m ²		
4	On door frames	2	m ²		
<u>ON WOOD</u> <u>Three coats polyurethane semi-gloss varnish</u>					
5	On doors (external)	6	m ²		
Carried Forward to Summary of Section No.1					
Section No.1 Guard House					
Bill No.12					
Paintwork					
2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					
Item No					Amount
	Section No.1 Guard Houses				
Bill No.	SECTION SUMMARY				
1	Earthworks (Provisional)				
2	Concrete & Formwork				
3	Masonry				
4	Waterproofing				
5	Roof Coverings, etc.				

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

6	Carpentry & Joinery				
7	Ceilings, Partitions & access flooring				
8	Ironmongery				
9	Metalwork				
10	Plastering				
11	Tiling				
12	Paintwork				
Carried to Final Summary					
Section No.1 Guard House 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					
Item No		Quantity	Unit	Rate	Amount
Section No.2					
OTHER ITEMS/SERVICES					
BILL No.1					
<u>OTHER ITEMS/SERVICES</u>					
<u>Electrical Installation</u>					
1	Supply and installation of electrical pipework	1	No		
<u>Carport</u>					
2	Supply and installation of a net shade carport with coverage of 3 cars at Moletji branch office	1	No		
Carried Forward to Final Summary					R
Section No.2 PROVISIONAL SUMS Bill No.1 2 NEW GATE HOUSES FOR MOLEMOLE MUNICIPALITY					

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

				Amount
Section No.	FINAL SUMMARY			
	1	GUARD HOUSES		
	2	OTHER ITEMS/SERVICES		
		SUB-TOTAL		
		Add Value Added Tax (VAT) 15%	15%	
		TOTAL RFQ AMOUNT		

2. The following documentation should accompany your quotations:

- a) The recent up-to-date central supplier database (CSD) registration report detailing all compliance requirements; [Last verified between the **advert date** and the **closing date**]
- b) Valid Tax Compliance status pin
- c) Fully signed and completed declaration of interest form [downloadable from www.molemole.gov.za]
- d) Fully signed and completed MBD 9 form [downloadable from www.molemole.gov.za]
- e) Fully signed and completed MBD 6.2 AND Annex C form [downloadable from www.molemole.gov.za]
- f) A copy of a valid letter of good standing from the compensation commissioner (**Nature of business: Building maintenance/building construction**)
- g) A valid certified copy of CIDB grading of 1 GB

N.B. Failure to attach the above documents will disqualify the bidder from further evaluation.

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

1. Stage 1: Evaluation on local content

1.1 Evaluation on local content

Under local content stage of evaluation, the following should be completed and duly signed, bidders must meet the minimum threshold of local content as required by the national treasury for **Cabling**

- MBD 6.2
- Annex C (Downloadable from municipal website under tenders/download files)
- Authorisation/Exemption letter by the DTI (where applicable)

Local Content formula

$$LC = [1 - x / y] * 100$$

Where

X is the imported content in Rand

Y is the bid price in Rand excluding value added tax (VAT)

3. Evaluation on functionality

Under functionality, Bidders must achieve a minimum of 80% of the total points (rounded to the nearest decimal point) for functionality (quality) in order to be considered for further evaluation in stage 2 (Evaluation on Price and Specific Goal)

Criteria	Weights	Applicable values
Proof of RELEVANT experience by the bidding company in repairs and maintenance of buildings OR construction of buildings. Attach appointment letters with contactable references on Clients company letterhead. Attach a maximum of 05 projects only	80	Poor = 1 Average = 2 Good = 3
MS(Microsoft) Project implementation programme detailing -activities and time frames -key milestones of the project	10	Very good = 4 Excellent = 5
Specify warranty period on each item constructed or supplied on the company's letterhead	10	
Total	100	

4. Stage 3: Evaluation on Price and Specific Goals

- Bidders must attach the following supporting documents to claim points. Failure to attach the valid documents points shall not disqualify the Bidder from further evaluation; but only points will be forfeited.


Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner

Preference Points for specific Goals	Means of Verification	Points
People or Business residing within Molemole Local Municipality	Statement of municipal rates or Proof of residents from Traditional Authority	5
Woman- Ownership of more than 50%	Identification Document and Company and Intellectual Property Commission (CIPC) document	5
People with Disability	Medical Report indicating Disability	5
Youth (18 to 34 years)	Identification Document	5

The following conditions will apply:

- a) Quotations must be on an official letterhead of the company
 - b) Price(s) quoted must be valid for fourteen (14) days from the date of this offer
 - c) Incomplete quotations will be disqualified from further evaluation
 - d) Payment will be effected within 30 days of receipt of invoice.
 - e) Quotations will be evaluated on 80/20 preference point system. Whereas 80 points will be for price and 20 will be for specific goal as per PPPFA of 2022,
 - f) The bidder needs to ensure that there is skills transfer.
 - g) The Municipality is not bound to accept the lowest or any bid and reserve the right to not accept any quotation either wholly or a part thereof;
- Kindly direct all technical enquiries to **Mpe I. at 015 501 2300** between 08:00 and 16:30. All quotations should be submitted at Mogwadi Municipal RFQ Box by the **31 July 2023 at 11h00**, clearly marked "**Construction of two (2) guard houses and carport**"
 - No quotations would be accepted after the closing date.
 - Molemole municipality reserves the right to accept any quotations.



MR. K.E MAKGATHO
MUNICIPAL MANAGER
COPR:8/1/103

Vision: A developmental people driven organization that serves its people

Mission: To provide essential and sustainable services in an efficient and effective manner