HEAD OFFICE

303 Church Street Private Bag X 44 MOGWADI 0715

Telephone : (015) 501 0243/4 Fax no : (015) 501 0419 E-mail: info@molemole.gov.za



MOREBENG BRANCH OFFICE

25 Cnr. Roets & Viviers Street

MOREBENG 0810

Telephone : (015) 501 2301 / (015) 501 2371

Fax no : (015) 397 4334

www.molemole.gov.za

ALL CORRESPONDENCE TO BE ADDRESSED TO THE

Ralephenya T.D

Ref: Tech 8/1/1/07

Date: 12 May 2025

REQUEST FOR QUOTATION

MOLEMOLE MUNICIPALITY IS HEREBY INVITING QUOTATIONS FROM SUITABLE SERVICE PROVIDERS WHO ARE REGISTERED ON THE CENTRAL DATABASE FOR REPAIRS AND MAINTENANCE OF FATIMA OUTLINING INTERNAL STREETS STORMWATER CONTROL AND ANCILLARY WORKS IN FATIMA VILLAGE AS PER THE BELOW SPECIFICATION.

Description	Unit	Quantity	Rate	Amount
Stormwater Channel Crossing				
(a) Cutting asphalt/seal [saw cut the existing asphalt surface of 30 to 50mm thickness]	m²	310	1225	
(a) Excavations for Stormwater Channel Crossing Footings 5x(8.0m x 0.45m x 0.25m)	m³	4,5		
(b) Cast in-situ concrete Stormwater Channel Crossing Footings 5x(8.0m x 0.4m x 0.3m) of Class 30/19 concrete	m ³	4,8		
(c) Cast in-situ concrete Stormwater Channel Crossing 5x(6.0m x 8.0m x 0.3m) of Class 30/19 concrete	m³	72		
(d) Reinforcing steel for above mentioned concrete cover at 50mm cover (Mesh Ref. no. 617)	kg	1481		
(e) Stormwater control crossing Walkway Railing Barrier (Posts: SHS100x6 Rails: RHS152x76x5 Panel: Round Bar Ø20 Post	no.	20		

Centres: 2400mm Railing Gaps: 96m)				
(f) Retaining wall of environmental friendly materials (100m x 1.8m x 0.3m)	m³	54		
(g) Backfilling the retaining wall ausing imported and existing materials	m³	27		
Ancillary Works				
STORMWATER CONCRETE V-DRAIN[L.I]]		10	l
Excavations for Stormwater Concrete V- Drain (100m x 3.0m x 0.5m)	m ³	150		
surface bed treatment including compaction to 93% Mod AASHTO density (100m x 3.9m x 0.1m)	m ³	30		
Cast in-situ concrete V-Drain (100m x 3.0m x 0.4m) of Class 25/19 concrete	m ³	120		
Cast in-situ concrete Chute (30m x 1.5m x 0.4m) of Class 25/19 concrete	m ³	18		
Reinforcing steel for above mentioned concrete cover at 50mm cover (Mesh Ref. no. 395)	kg	800		
(d) Filter fabric (kaytech grade A4 or similar)	m²	1200		
Sub-Total				
VAT @ 15%				
Total project cost (Including VAT)				

- 1. The following documentation should be attached to the quotations:
- a. The recent up-to-date central supplier database (CSD) registration report detailing all compliance requirements; [Last verified between the **advert date** and the **closing date**]
- b. Valid Tax Compliance status pin
- c. CIDB Grading 1CE
- d. Fully signed and completed declaration of interest form [downloadable from www.molemole.gov.za]
- e. Fully signed and completed MBD 9 form [downloadable from www.molemole.gov.za]

Stage 2: Evaluation on Price and Specific Goals

Bidders must attach following supporting documents to claim points. Failure to attach the
valid documents shall not disqualify the Bidder from further evaluation; but only points will
be forfeited.

Preference Points for specific Goals	Means of Verification	Points	
People or Business residing within Molemole Local Municipality	Statement of municipal rates or Proof of residents from Traditional Authority	5	
Woman-ownership of more than 50%	Identification Document and Company and Intellectual Property Commission (CIPC) document.	5	
People with Disability	Medical Report indicating Disability	5	
Youth (18 to 34 years)	Identification Document	5	

2. THE FOLLOWING CONDITIONS WILL APPLY:

- a) Quotations must be on an official letterhead of the company
- b) Price(s) guoted must be valid for fourteen (14) days from the date of this offer
- c) Incomplete quotations will be disqualified from further evaluation
- d) Payment will be effected within 30 days of receipt of invoice.
- e) Quotations will be evaluated on 80/20 preference point system. Whereas 80 points will be for price and 20 will be for specific goal as per PPPFA of 2022,
- f) The Municipality is not bound to accept the lowest or any bid and reserve the right to not accept any quotation either wholly or a part thereof.

Kindly direct all technical enquiries to **Mr. Mabasa V.P** at 015 501 2304 between 08:00 and 16:30. All quotations should be submitted at Mogwadi Municipal RFQ Box by the **19 May 2025** at 11h00, clearly marked "**REPAIRS AND MAINTENANCE OF FATIMA**" No quotations will be accepted after the closing date. Molemole municipality reserves the right to accept any quotations.

Mr Makgatho K.E

MUNICIPAL MANAGER