


HEAD OFFICE

303 Church Street
Private Bag X 44
MOGWADI 0715
Telephone : (015) 501 0243/4
Fax no : (015) 501 0419
E-mail: info@molemole.gov.za



Molemole Municipality

ALL CORRESPONDENCE TO BE ADDRESSED TO THE MUNICIPAL MANAGER

MOREBENG BRANCH OFFICE

25 Cnr. Roets & Viviers Street
MOREBENG 0810
Telephone : (015) 397 4333 / (015) 397 4327
Fax no : (015) 397 4334

www.molemole.gov.za

Enquiries: JimmyM

Reference: CMS/02

24 MARCH 2014

CALL FOR QUOTATIONS FROM SERVICE PROVIDERS FOR RENOVATION OF RAMOKGOPHA STADIUM.

Specification for this service:

Kindly refer to the attachment.

The following documentation should accompany your quotations:

- a) Company registration certificate
- b) A valid Tax clearance certificate
- c) Completed declaration form (downloadable on municipal website)
- d) Valid BEE certificate
- e) Minimum of 2 contactable references for related service.

The following conditions will apply:

- Quotation must be on an official letterhead of the company;
- Price(s) quoted must be valid for at least thirty (30) days from the date of this offer;
- Price (s) must be firm and inclusive of VAT;
- A firm delivery date must be indicated.
- Quotations will be evaluated on 80/20 preference point system. Whereas 80 points will be for price and 20 for preference as per PPPFA of 2000, BBEEA of 2003 and preferential procurement regulation of 2001.

For any technical enquiries please contact Mr Nyoffu E at 015 501 0243 between 08:00 and 16:00. All quotations should be submitted at Mogwadi Municipal Tender Box by the latest 01 April 2014 at 12H00, clearly marked **RENOVATION OF RAMOKGOPHA**. No quotation will be accepted after the closing date.

Molemole municipality is not bound to accept the lowest or any bid and proposal and reserves the right to accept any proposal either wholly or part thereof.

**MADIBANA M
ACTING MUNICIPAL MANAGER**

Vision: A developmental people driven organization that serves its people"

Mission: To provide essential and sustainable services in an efficient and effective manner.

SPECIFICATION FOR RENOVATION OF RAMOKGOPA STADIUM

Description	Unit	Quantities	Unit price	Total price
<u>P & G's</u>				
Preliminaries and General		Sum		
<u>Roof covering</u>				
0.6mm "Chromadek" roof sheeting fixed to timber purlins . N.B: All timber work including purlins should not exceed 900mm centre to centre and the roof should overlap the wall by 300mm	M ²	52		
Fixing of the roof at the male toilet	NO	1		
<u>Gutters</u>				
Steel gutters standard fixed to timber purlins and connected to the down pipe.	m	11		
<u>GLAZING</u>				
4mm rough float glass with party complete	M ²	1		
<u>Plumbing</u>				
Supply and fitting of the following:				
50mm uPvc pipe	M	12		
50mm elbows	NO	5		
110mm uPvc pipe	M	8		
Toilet seat	NO	1		
Fixing of the existing urinal	Item	1		
Unblocking and testing of the entire sewer system and water supply.	item	1		
<u>PAINTING</u>				
<u>ON WOOD</u>				
One coat primer, one coat universal undercoat and two coats super acrylic PVA paint				
On doors	M ²	14		

<p><u>ON METAL</u></p> <p><u>Spot priming defects in pre primed surfaces with zinc chromate primer and applying one undercoat and two coats alkyd enamel paint on steel.</u></p> <p>On steel door frames, steel window frames, steel burglar doors, steel window sieves, Gutters and down pipes.</p> <p><u>ON PLASTIC</u></p> <p><u>One coat super acrylic PVA paint</u></p> <p>On blumbing fittings and pipes</p> <p><u>ON WALLS</u></p> <p><u>One coat alkali resistant primer, one undercoat and two coats eggshell enamel paint</u></p> <p>On beam filling(internal plastered wall)</p> <p>On existing internal wall,</p> <p><u>ON PLASTIC</u></p> <p><u>Two coats alkyd enamel paint on plastic.</u></p> <p>On uPVC plumbing pipes & fittings</p> <p>NB: all paints to be used must be the same as the existing paints on site in color.</p>	<p>M²</p> <p>M²</p> <p>M²</p> <p>M²</p> <p>M²</p> <p>M²</p> <p>M²</p>	<p>22</p> <p>5</p> <p>\</p> <p>12</p> <p>168</p> <p>5</p>		
<p><u>Community Liason Officer(Provisional sum)</u></p> <p>Provide the sum of R5000 (five thousand rands only) for the community liason officer.</p>	<p>item</p>	<p>1</p>		<p>5000.00</p>
<p><u>BRICK WORK</u></p> <p>230mm wall for beamfilling</p>	<p>M²</p>	<p>12</p>		
<p><u>RAZOR WIRE</u></p> <p>Supply and installation of razor wire at the stadium.</p>	<p>M</p>	<p>20</p>		

Supply and welding of 1.4m high steel poles N.B:The razor wire should be fixed to the 1.4m high steel welded on the existing horizontal poles.	NO	5		
PRICE				
VAT @ 14%				
SUB-TOTAL PRICE				

SUPPLY, DELIVERY AND INSTALLATION OF ELECTRICAL MATERIALS

Note: unless otherwise specified the material shall be in accordance to the specifications listed in the municipal small works contract (Bill of Quantity).

1. Work specification

Notes:

- a) All work shall be in accordance with the relevant specified specification (WIRING CODE SANS 10142).
- b) All labour cost shall be included in quoted rate.

2. Preliminaries

- a) The specific contractor shall supply and install all relevant electrical apparatus in accordance with the specified wiring code.
- b) All material shall be SABS approved.

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
CLEANING OF MINI-SUBSTATION					
1	Transportation 1.1 RAMOKGOPA STADIUM	Sum	1		
2	SUPPLY AND INSTALLATION				
	2.1. 6 Mode Distribution Board	No	1		
	2.2. 2x4 complete switch	No	2		
	2.3. 1m x fluorescent light	M	8		

	2.4. 1.5mm Red, white, black and bare earth conductor.	M	4 each		
	2.5. 2.5mm Red, black and bare earth.	M	4 each		
	2.6. 63amp Earth Leakage				
	2.7. Surge protection	No	1		
	2.8. 10amp circuit breaker	No	3		
	2.9. 20amp circuit breaker	No	1		
3.	Wall grinding and installation of 20mmx 6m PVC conduit.	No	25		
Sub Total					

BILL OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Transportation 1.1 RAMOKGOPA STADIUM	Sum	1		
2	SUPPLY AND INSTALLATION				
	2.1. 16 way Wall Distribution Board	No	1		
	2.2. 2x4 complete 2 lever switch (Crabtree)	No	2		
	2.2. 2x 4 complete single lever switches (Crabtree)	No	2		
	2.3. 1m x fluorescent light	M	8		
	2.4. 1.5mm Red, white, black and bare earth conductor.	M	5 each		
	2.5. 2.5mm Red, black and bare earth.	M	1 each		
		No	1		
	2.6. 63amp Earth Leakage (cbi)	No	3		
	2.7. Surge protection	No	3		
	2.8. 10amp circuit breaker (cbi)	No	3		

	2.9. 20amp circuit breaker (cbi)	No	2		
3.	Toilets(outside)				
	3.1. 2x4 complete single lever switch (Crabtree)	No	2		
	3.2. 1mx fluorescent light	No	12		
	3.3. loop in box 4 way	No	24		
	3.4. 20mm female adaptors	No	20		
	3.5. 20mm couplings	No	25		
	3.6. saddling	No	30		
	3.7. ceiling nails 3.5x 35mm	No	60		
	3.8. M4 screws	No	20		
	3.9. 4mm furrels	No	20		
	3.10. Insulation tape	No	2		
3.	Wall grinding, installation and recovering of 20mmx 6m PVC conductors.	No	30		
Sub Total					

Summary of Bill of Quantity

Project name:

ITEM	DESCRIPTION	LABOUR AMOUNT	MATERIAL AMOUNT
1	Transportation Ramokgopa Stadium		
2	Supply, Delivery and Installation of Electrical		

	Materials.		
3.	Wall grinding, installation and recovering of PVC conduit.		
Sub- Total			
Total cost (Excluding V.A.T)			
V.A.T @ 14 %			
Total cost (Including V.A.T)			