

HEAD OFFICE

303 Church Street
 Private Bag X 44
 MOGWADI 0715
 Telephone : (015) 501 0243/4
 Fax no : (015) 501 0419
 E-mail: info@molemole.gov.za



ALL CORRESPONDENCE TO BE ADDRESSED TO THE MUNICIPAL MANAGER

MOREBENG BRANCH OFFICE

25 Cnr. Roets & Viviers Street
 MOREBENG 0810
 Telephone : (015) 397 4333 / (015) 397 4327
 Fax no : (015) 397 4334

www.molemole.gov.za

Enquiries: Mabote NJ

Reference: 8/1/1:TCS-03

24 March 2016

CALL FOR QUOTATION FROM SUITABLE SERVICE PROVIDERS WHO ARE LISTED IN MLM'S DATABASE FOR MAINTENANCE OF BROEKMAN INTERNAL STREET AND STORMWATER

Description	Units	QTY	Rate	Amount
Social Obligations				
a) Provisional Sum for the payment of the CLO (R3500.00)	Prov. Sum			R 10500-00
Handling Cost of the Above Item.	%			R 1050-00
a) Provisional Sum for Cost of attending Project Steering Committee meetings (5 committee members R3000.00)	Prov. Sum			R 3000-00
Handling Cost of the Above Item.	%			R 300-00
Prefabricated Culverts				
1. Excavation:				
Excavating materials situated within the following depth ranges below the surface level:				
(i) 0m up to 1.5m	m ³	60		
2. Backfilling and compaction to 95% MOD ASHTO using the following:				
(a) Excavated Materials	m ³	25		
(b) Imported Materials	m ³	35		
3. Concrete Pipe Culverts:				
(b) on Class B bedding:				
(ii) 900mm dia. (Class 100D)	m	13		
10. Cast in-situ Concrete and Formwork: in 150mm inlet and outlet structures, skewed ends, wing walls, catchpits, thrust and anchor blocks Class U2 finish for (i) Class 25/19 concrete and concrete testing	m ³	15		
11. Reinforcing Steel using:				
(a) Welded Steel Fabric - Mesh Ref. No. 880	kg	400		
(b) Welded Steel Fabric - Mesh Ref. No. 395	kg	150		

Vision: A developmental people driven organization that serves its people"

Mission: To provide essential and sustainable services in an efficient and effective manner.

15. MASS EARTHWORKS				
(a) Pavement layers constructed from gravel taken from cut or borrow, including free-haul up to 6,0 km				
(a) Gravel sub base layer compacted to:				
(i) 93% of modified AASHTO density, compacted layer thickness 150mm	m ³	400		
(c) Gravel base (unstabilized gravel) compacted to:				
(ii) 95% of modified AASHTO density, compacted layer thickness 150 mm	m ³	150		
SubTotal				
V.A.T @ 14 %				
Total project cost (Including V.A.T)				

The following documentation should accompany your quotations:

- a) Company registration certificate and certified copies of all company directors
- b) An original valid Tax clearance certificate
- c) Completed declaration form (downloadable on municipal website)
- d) An original or certified copy of valid BBBEE certificate (if applicable)
- e) CIDB grade: 1CE

The following conditions will apply:

- Quotation must be on an official letterhead of the company;
- Price(s) quoted must be valid for at least thirty (30) days from the date of this offer;
- Price (s) must be firm and inclusive of VAT;
- Delivery must be made within 14 days. Failure to deliver within 14 day may result in the municipality cancelling its order.
- Payment will be effected within 30 days of receipt of invoice.

Kindly direct all technical enquiries to **Mr. Hlungwani G at 015 501 2338** between **08:00** and **16:30**. All quotations should be submitted at Mogwadi Municipal Tender Box by the latest **1 April 2016 at 10:00**, clearly marked "Broekman internal streets and storm water ". No quotation will be accepted after the closing date.

Molemole municipality reserves the right to accept any quotation.



Mr. Makhura N.I
MUNICIPAL MANAGER