

HEAD OFFICE

303 Church Street  
Private Bag X 44  
MOGWADI 0715  
Telephone : (015) 501 0243/4  
Fax no : (015) 501 0419  
E-mail: info@molemole.gov.za



**Molemole Municipality**

ALL CORRESPONDENCE TO BE ADDRESSED TO THE MUNICIPAL MANAGER

MOREBENG BRANCH OFFICE

25 Cnr. Roets & Viviers Street  
MOREBENG 0810  
Telephone : (015) 397 4333 / (015) 397 4327  
Fax no : (015) 397 4334

[www.molemole.gov.za](http://www.molemole.gov.za)

Enquiries: Mabote NJ

Reference: 8/1/1: TCS-04

24 March 2016

**CALL FOR QUOTATION FROM SUITABLE SERVICE PROVIDERS WHO ARE LISTED IN MLM'S DATABASE FOR MAINTENANCE OF EISLEBEN INTERNAL STREETS AND STORMWATER**

Description	Units	QTY	Rate	Amount
<b>Social Obligations</b>				
(a) Provisional Sum for the payment of the CLO (R3500.00)	Prov. Sum			R 10500-00
Handling Cost of the Above Item.	%			R 1050-00
(a) Provisional Sum for Cost of attending Project Steering Committee meetings (5 committee members R3000.00)	Prov. Sum			R 3000-00
Handling Cost of the Above Item.	%			R 300-00
<b>Prefabricated Culverts</b>				
1. Excavation:				
Excavating materials situated within the following depth ranges below the surface level:				
(i) 0m up to 1.5m	m <sup>3</sup>	70		
2. Backfilling and compaction to 95% MOD ASHTO using the following:				
(a) Excavated Materials	m <sup>3</sup>	30		
(b) Imported Materials	m <sup>3</sup>	40		
3. Concrete Pipe Culverts:				
(b) on Class B bedding:				
(ii) 900mm dia. (Class 100D)	m	30		
10. Cast in-situ Concrete and Formwork: in 150mm inlet and outlet structures, skewed ends, wing walls, catchpits, thrust and anchor blocks Class U2 finish for (i) Class 25/19 concrete and concrete testing	m <sup>3</sup>	18		

Vision: A developmental people driven organization that serves its people"

Mission: To provide essential and sustainable services in an efficient and effective manner.

11. Reinforcing Steel using:				
(a) Welded Steel Fabric - Mesh Ref. No. 880	kg	1010		
(b) Welded Steel Fabric - Mesh Ref. No. 395	kg	136		
15. MASS EARTHWORKS				
(a) Pavement layers constructed from gravel taken from cut or borrow, including free-haul up to 6,0 km				
(a) Gravel sub base layer compacted to:				
(i) 93% of modified AASHTO density, compacted layer thickness 150mm	m <sup>3</sup>	350		
(c) Gravel base (unstabilized gravel) compacted to:				
(ii) 95% of modified AASHTO density, compacted layer thickness 150 mm	m <sup>3</sup>	100		
Sub Total				
V.A.T @ 14 %				
Total project cost (Including V.A.T)				

**The following documentation should accompany your quotations:**


- Company registration certificate and certified copies of all company directors
- An original valid Tax clearance certificate
- Completed declaration form (downloadable on municipal website)
- An original or certified copy of valid BBBEE certificate (if applicable)
- CIDB: grade 1 CE

**The following conditions will apply:**

- Quotation must be on an official letterhead of the company;
- Price(s) quoted must be valid for at least thirty (30) days from the date of this offer;
- Price (s) must be firm and inclusive of VAT;
- Delivery must be made within 14 days. Failure to deliver within 14 day may result in the municipality cancelling its order.
- Payment will be effected within 30 days of receipt of invoice.

Kindly direct all technical enquiries to **Mr. Hlungwani G** at **015 501 2338** between **08:00** and **16:30**. All quotations should be submitted at Mogwadi Municipal Tender Box by the latest **1 April 2016 at 10:00**, clearly marked "Eisleben internal streets". No quotation will be accepted after the closing date.

Molemole municipality reserves the right to accept any quotation.

  
**Mr. Makhura N.I**  
**MUNICIPAL MANAGER**

Vision: A developmental people driven organization that serves its people"

Mission: To provide essential and sustainable services in an efficient and effective manner.